

PROJECT NO. 2018

DATE: October 29, 2020

**ADDENDUM NO. 2  
BOUTWELL AUDITORIUM EXHIBITION HALL REROOFING**

**BIDS RECEIVED:**  
**TIME: 2:00 P.M.**  
**DATE: November 5, 2020**  
**Room 215 City Hall**

**ARCHITECTURAL DIVISION**  
**DEPT. OF CAPITAL PROJECTS**  
**DENISE BELL, DIRECTOR**  
**ALAN TERRY OGLESBY, NCARB, CITY ARCHITECT**

---

THIS ADDENDUM IS DIRECTED TO ALL PRIME BIDDERS, AND ALL OTHERS TO WHOM DRAWINGS AND SPECIFICATIONS HAVE BEEN ISSUED.

THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS. THE FOLLOWING CONDITIONS TAKE PRECEDENCE OVER ANY CONFLICTING CONDITIONS IN THE DRAWINGS AND SPECIFICATIONS. THE DRAWINGS AND SPECIFICATIONS ARE HEREBY AMENDED IN THE FOLLOWING PARTICULARS.

---

**CLARIFICATIONS and CORRECTIONS**

**DRAWING**

- 1) Sheet A-1, Roofing Note 7 shall be amended to include the following language: "CONTRACTOR SHALL INSTALL MANUFACTURER'S RECOMMENDED AND PROVIDED 1/2" THICK PRIME COVERBOARD FULLY ADHERED TO THE TOP SURFACE OF THE NEW INSULATION AS REQUIRED FOR SYSTEM WARRANTY COVERAGE."
- 2) Sheet A-1, Roofing Note 15 shall be deleted and the following language substituted: "EXISTING ROOF SCUTTLE. CONTRACTOR SHALL REMOVE EXISTING SCUTTLE AND PROVIDE NEW CURB HEIGHT EXTENSION (10" MINIMUM) TO PROVIDE SUFFICIENT HEIGHT FOR TAPERED INSULATION AT CURB. CONTRACTOR SHALL RELOCATE EXISTING CONDUIT AND WIRING CURRENTLY PENETRATING THE SIDES OF THE EXISTING CURB SO THAT THE CONDUIT INSTEAD VERTICALLY PENETRATES THE ROOF DECK AND ROOF MEMBRANE. CONTRACTOR SHALL PROPERLY SEAL CONDUIT PENETRATION USING MANUFACTURER-PROVIDED PREFORMED BOOTS AND SEALANT AND RECOMMENDED DETAILS. CONTRACTOR SHALL LAP MEMBRANE OVER EDGE OF CURB AND SECURE TO THE INSIDE FACE AND INSTALL NEW METAL COUNTERFLASHING AROUND CURB USING MANUFACTURER'S RECOMMENDED DETAILS. CONTRACTOR SHALL REINSTALL EXISTING SCUTTLE."

**END OF ADDENDUM**